

**WEST KERN WATER DISTRICT
SOUTH WELL FIELD ACCESS ROAD MAINTENANCE PROJECT, 27-4400
ADDENDUM NO. 1**

DATE: MONDAY, OCTOBER 5, 2026

This Addendum No. 1 modifies and clarifies the Request for Bids (RFB) as follows. All other requirements of the RFB remain unchanged.

Construction Water: The District will make construction water available to the Contractor at or near the location identified in this link: [View on Apple Maps](#). The Contractor shall provide all equipment, hoses (2 ½" fire hose connection), tanks, pumps, fittings, and other means necessary to obtain, transport, and apply the water. An approved air gap shall be maintained at the water connection at all times. Access to the water source shall be coordinated with the District.

Fire Prevention and Safety: The Contractor is responsible for providing and maintaining all required fire-prevention and fire-safety measures during the Work and for complying with applicable site conditions, laws, and regulations.

Temporary Restroom Facilities: The Contractor is responsible for providing and maintaining any temporary restroom facilities required for its personnel during the Work.

Compaction Testing: The District will not require laboratory or field-density compaction testing for this Project. The Contractor remains responsible for properly watering, grading, and compacting the Class II aggregate base to produce a firm, stable, and uniform finished roadway.

Existing Roadway: Removal or excavation of the existing roadway surface is not required. The Contractor shall rough grade and prepare the existing roadway as necessary before placing the Class II aggregate base.

Finished Roadway Slope: The finished roadway shall be crowned to provide approximately two percent (2%) cross slope from the crown toward each edge. The Contractor shall produce a smooth and uniform finished surface within the specified roadway width and compacted depth.

Underground Service Alert: The Contractor is responsible for complying with all Underground Service Alert requirements, including making the required notification before beginning applicable Work. The Contractor shall protect existing utilities and facilities and immediately notify the District of any conflict, damage, or previously unidentified facility.

**WEST KERN WATER DISTRICT
SOUTH WELL FIELD ACCESS ROAD MAINTENANCE PROJECT, 27-4400
ADDENDUM NO. 1**

Equipment and Material Storage: The District will allow the Contractor to store equipment and materials on District property near the end of the project limits. The specific storage area shall be coordinated with and authorized by the District. All equipment and materials will be stored at the Contractor's sole risk, and the Contractor is responsible for security and protection against theft, vandalism, damage, or loss.

Aggregate Base Material Requirements: No contamination testing or contamination report is required for the imported aggregate base material. Recycled aggregate base is not acceptable. The proposed material shall be non-recycled aggregate base meeting Caltrans Class II Aggregate Base requirements. The Bidder shall submit documentation from the proposed material supplier with its bid verifying that the material meets Caltrans Class II Aggregate Base requirements.

Bidders shall account for these clarifications in preparing their bids and acknowledge receipt of this Addendum in the space provided on the Bid Form. All other requirements of the Contract Documents remain unchanged.